



Mountable accessories (to be ordered separately):



The fully wired and tested contactor assembly includes the following components:



The connecting cables are not shown.

Accessories

Order No.

14	Auxiliary switch block, front	3RH19 11-1...
16	Surge suppressors	3RT19 16-1...
17	3-phase feeder terminals	3RA19 13-3K

Individual parts

Order No.

K1¹⁾

K3²⁾


K2²⁾

1 2 3	Contactors, 5.5 kW	3RT10 15	3RT10 15	3RT10 15
1 2 3	Contactors, 7.5 kW	3RT10 17	3RT10 17	3RT10 15
7	Solid-state time-delay auxiliary switch block, front	3RT19 16-2G.51		
9	Auxiliary switch block with 1 unassigned NO contact	3RH19 11-1BA10		
4 5 6	Assembly kit	3RA19 13-2B		
The assembly kit contains:				
4	Mechanical interlock			
5	3 connecting clips			
6	Wiring modules on the top and bottom for connecting the main and control conducting paths			


¹⁾ Use version with 1 NO.

²⁾ Use version with 1 NC.

Mountable accessories (to be ordered separately):



The fully wired and tested contactor assembly includes the following components:



Accessories

Order No.

- | | | |
|----|--|----------------|
| 4 | Mechanical interlock, lateral | 3RA19 24-2B |
| 7 | Solid-state time-delay auxiliary switch block, front ¹⁾ | 3RT19 26-2G... |
| 12 | Mechanical interlock, front | 3RA19 24-1A |
| 15 | Auxiliary switch block, lateral | 3RH19 21-1EA.. |
| 16 | Surge suppressors | 3RT19 26-1.... |
| 17 | 3-phase feeder terminal ²⁾ | 3RV19 15-5A |
| 18 | 3-phase busbar ²⁾ | 3RT19 26-4CC20 |
| 19 | Push-in lug ³⁾ for timing relay screw fixing | 3RP19 03 |

4)

Individual parts

- | | Order No. | K1 | K3 | K2 |
|-------|---|----------------|----------|----------|
| 1 2 3 | Contactors, 11 kW | 3RT10 24 | 3RT10 24 | 3RT10 24 |
| 1 2 3 | Contactors, 15/18.5 kW | 3RT10 26 | 3RT10 26 | 3RT10 24 |
| 8 | Timing relay, lateral | 3RP15 74-1N.30 | | |
| 9 | Auxiliary switch block with 1 unassigned NO contact | 3RH19 21-1CA10 | | |
| 10 | Auxiliary switch block for local control | | | |
| | - 2 units | 3RH19 21-1CA01 | | |
| | - 3 units | 3RH19 21-1CA10 | | |
| 5 6 | Assembly kit | 3RA19 23-2B | | |

The assembly kit contains:

- 5 Connecting clips
- 6 Wiring modules on the top and bottom for connecting the main and control conducting paths


¹⁾ Generally possible. If a solid-state time-delay auxiliary switch block is mounted onto the front of K3, a standard auxiliary switch block can only be mounted onto the side.

²⁾ 17 and 18 can only be mounted with contactors with screw terminal (coil).


³⁾ Not included in the scope of supply of the preassembled contactor assemblies; can be ordered as an accessory.

⁴⁾ See "Monitoring and Control Devices: 3RP, 7PV Timing Relays --> 3RP15 Timing Relays in Industrial Enclosure, 22.5 mm".

Mountable accessories (to be ordered separately):



The fully wired and tested contactor assembly includes the following components:



Accessories

Order No.

4	Mechanical interlock, lateral Depth compensation required K3: 1.5 mm; K2: 0 mm ¹⁾	3RA19 24-2B
7	Solid-state time-delay auxiliary switch block, front ²⁾	3RT19 26-2G...
15	Auxiliary switch block, lateral	3RH19 21-1EA...
16	Surge suppressors	3RT19 26-1.... 3RT19 36-1....
17	3-phase feeder terminals	3RV19 35-5A
18	3-phase busbars	3RV19 35-1A
19	Push-in lug ³⁾ for timing relay screw fixing	3RP19 03 ⁴⁾

Individual parts

		Order No.	K1	K3	K2
1 2 3	Contactors, 22/30 kW	3RT10 34	3RT10 34	3RT10 26	
8	Timing relay, lateral	3RP15 74-1N.30			⁴⁾
9	Auxiliary switch block with 1 unassigned NO contact	3RH19 21-1CA10			
10	Auxiliary switch block for local control				
	- 2 units	3RH19 21-1CA01			
	- 3 units	3RH19 21-1CA10			
11	Base plate	3RA19 32-2E			
6	Assembly kit	3RA19 33-2C			

The assembly kit contains the star jumper on the top and the wiring module on the bottom for connecting the main current paths.


¹⁾ Use the 3RA19 32-2B base plate for this configuration.

²⁾ Generally possible. If a solid-state time-delay auxiliary switch block is mounted onto the front of K3, a standard auxiliary switch block can only be mounted onto the side.


³⁾ Not included in the scope of supply of the preassembled contactor assemblies; can be ordered as an accessory.

⁴⁾ See "Monitoring and Control Devices: 3RP, 7PV Timing Relays --> 3RP15 Timing Relays in Industrial Enclosure, 22.5 mm".

Mountable accessories (to be ordered separately):



The fully wired and tested contactor assembly includes the following components:



The connecting cables are not shown.

Accessories

Order No.

- | | | |
|----|--|----------------------------------|
| 4 | Mechanical interlock, lateral | 3RA19 24-2B |
| 7 | Solid-state time-delay auxiliary switch block, front ¹⁾ | 3RT19 26-2G... |
| 12 | Mechanical interlock, front | 3RA19 24-1A |
| 15 | Auxiliary switch block, lateral | 3RH19 21-1EA. |
| 16 | Surge suppressors | 3RT19 26-1....
3RT19 36-1.... |
| 17 | 3-phase feeder terminals | 3RV19 35-5A |
| 18 | 3-phase busbars | 3RV19 35-1A |
| 19 | Push-in lug ²⁾ for timing relay screw fixing | 3RP19 03 |

3)

Individual parts

- | | |
|-------|--|
| 1 2 3 | Contactors, 37 kW |
| 1 2 3 | Contactors, 45 kW |
| 8 | Timing relay, lateral |
| 9 | Auxiliary switch block with 1 unassigned NO contact |
| 10 | Auxiliary switch block for local control
- 2 units
- 3 units |
| 11 | Base plate |
| 6 | Assembly kit |

Order No.

K1

K3

K2

- | | | |
|----------------|----------|----------|
| 3RT10 35 | 3RT10 35 | 3RT10 34 |
| 3RT10 36 | 3RT10 36 | 3RT10 34 |
| 3RP15 74-1N.30 | | 3) |
| 3RH19 21-1CA10 | | |
| 3RH19 21-1CA01 | | |
| 3RH19 21-1CA10 | | |
| 3RA19 32-2F | | |
| 3RA19 33-2B | | |

The assembly kit contains the star jumper on the top and the wiring module on the bottom for connecting the main current paths.


¹⁾ Generally possible. If a solid-state time-delay auxiliary switch block is mounted onto the front of K3, a standard auxiliary switch block can only be mounted onto the side.

²⁾ Not included in the scope of supply of the preassembled contactor assemblies; can be ordered as an accessory.

³⁾ See "Monitoring and Control Devices: 3RP, 7PV Timing Relays --> 3RP15 Timing Relays in Industrial Enclosure, 22.5 mm".

Mountable accessories (to be ordered separately):

The fully wired and tested contactor assembly includes the following components:



The connecting cables are not shown.

Accessories

Order No.

- 4** Mechanical interlock, lateral
Depth compensation required
K3: 0 mm; K2: 27.5 mm¹⁾ 3RA19 24-2B
- 7** Solid-state time-delay
auxiliary switch block, front²⁾ 3RT19 26-2G...
- 15** Auxiliary switch block, lateral 3RH19 21-1EA...
- 16** Surge suppressors 3RT19 .6-1...
- 19** Push-in lug³⁾ for timing relay
screw fixing 3RP19 03
- 20** 1-phase feeder terminals 3RA19 43-3L

4)

Individual parts

- 1 2 3** Contactors, 55 kW
- 1 2 3** Contactors, 75 kW
- 8** Timing relay, lateral
- 9** Auxiliary switch block with
1 unassigned NO contact
- 10** Auxiliary switch block for
local control
- 2 units
- 3 units
- 11** Base plate
- 6** Assembly kit

Order No.

- | K1 | K3 | K2 |
|----------------|----------|----------|
| 3RT10 44 | 3RT10 44 | 3RT10 3f |
| 3RT10 45 | 3RT10 45 | 3RT10 3f |
| 3RP15 74-1N.30 | | |
| 3RH19 21-1CA10 | | |
| 3RH19 21-1CA01 | | |
| 3RA19 42-2E | | |
| 3RA19 43-2C | | |

4)

The assembly kit contains the star jumper on the top and the wiring module on the bottom for connecting the main current paths.

¹⁾ Use the 3RA19 42-2B base plate for this configuration.

²⁾ Generally possible. If a solid-state time-delay auxiliary switch block is mounted onto the front of K3, a standard auxiliary switch block can only be mounted onto the side.

³⁾ Not included in the scope of supply of the preassembled contactor assemblies; can be ordered as an accessory.

⁴⁾ See "Monitoring and Control Devices: 3RP, 7PV Timing Relays --> 3RP15 Timing Relays in Industrial Enclosure, 22.5 mm".